

BRUHATH BANGALORE MAHANAGARA PALIKE

RAJARAJESHWARINAGARA ZONE

Name of work: Detailed Estimate for Providing and laying HDPE Water line in Ganesha Temple Block-3 in J P Park, Ward No 17.

Est. Cost in Lakhs :								49.93	
Sl. No.	Description	Unit	Dimensions				Qty.	Rate	Amount
			No.	L.	B.	D			
1	KSRB : Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. (Page No.5, Item No. 2.4 of KPWD SR 2013-14)								
	Asphalt Road	Cum	1	2000.00	0.45	1.00	900.00		
	Concrete Road		1	195.00	0.45	1.00	87.75		
	Asphalt Cross Cutting		320	7.50	0.45	1.00	1080.00		
	Concrete Cross Cutting		70	7.00	0.45	1.00	220.50		
	Total						2288.25	227.88	521446.00
	Basic Rate	211.00							
	Area weightage @ 8%	16.88							
	Total	227.88							
2	KSRB13-9.1 : Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 6.00 kgf/sq.cm working pressure 90mm outside diameter , compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications. Specification No.KBS 13.2.1 5.2 1 13.9 (I-13.73.3 P-102 of KPWD SR 2013-14)								
	For Main Line	Rmtr	1	2195.00			2195.00		
	Total						2195.00	501.12	1099958.00
	Basic Rate	464.00							
	Area weightage @ 8%	37.12							
	Total	501.12							
3	KSRB13-9.1 : Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 10.00 kgf/sq.cm working pressure 25mm outside diameter , compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications. Specification No.KBS 13.2.1 5.2 1 13.9 (I-13.76 P-103 of KPWD SR 2013-14)								
	Left side	Rmtr	195.0	6.00			1170.00		
	Right side		195.0	9.00			1755.00		
	Total						2925.00	106.92	312741.00
	Basic Rate	99.00							
	Area weightage @ 8%	7.92							
	Total	106.92							

Sl. No.	Description	Unit	Dimensions				Qty.	Rate	Amount
			No.	L.	B.	D			
4	KSRB13-3.2 : Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 20mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 (I-13.11, P- 95 of KPWD SR 2013-14)								
	For Delivery at End	Rmtr	390.0	1.20			468.00		
	Total						468.00	197.64	92496.00
	Basic Rate	183.00							
	Area weightage @ 8%	14.64							
	Total	197.64							
5	Providing and fixing 25mm dia nipple, complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	1	390.00			390.00		
	Total						390.00	32.10	12519.00
	Basic Rate	32.10							
	Total	32.10							
6	Providing and fixing reducer elbow 25mm to 20mm complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	2	390.00			780.00		
	Total						780.00	41.00	31980.00
	Basic Rate	41.00							
	Total	41.00							
7	Providing and fixing 20mm dia nipple, complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	1	390.00			390.00		
	Total						390.00	21.00	8190.00
	Basic Rate	21.00							
	Total	21.00							
8	Providing and fixing HDPE 90 x 32mm saddle with brass nuts and bolts including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications.								
		Nos	2	390.00			780.00		
	Total						780.00	350.00	273000.00
	Quotation Rate	350							
9	Providing and fixing 20mm dia union, complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	1	390.00			390.00		
	Total						390.00	54.45	21236.00
	Basic Rate	54.45							
	Total	54.45							

Sl. No.	Description	Unit	Dimensions				Qty.	Rate	Amount
			No.	L.	B.	D			
10	Providing and fixing 20mm dia hose collar, complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	2	390.00			780.00		
	Total						780.00	26.30	20514.00
	Basic Rate	26.30							
	Total	26.30							
11	Providing and fixing 20mm elbow, complete as per specifications.(Page XXXVIII of KPWD SR 2013-14)								
		Nos	2	390.00			780.00		
	Total						780.00	17.80	13884.00
	Basic Rate	17.80							
	Total	17.80							
12	Providing and fixing 20mm to 15mm reducer elbow, complete as per specifications. (Page XXXVIII of KPWD SR 2013-14)								
		Nos	2	390.00			780.00		
	Total						780.00	22.10	17238.00
	Basic Rate	22.10							
	Total	22.10							
13	Providing and fixing 20mm NP bib cock complete as per specifications. (Page XXII Sl No 617 of KPWD SR 2013-14)								
		Nos	1	390.00			390.00		
	Total						390.00	189.00	73710.00
	Basic Rate	189.00							
	Total	189.00							
14	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (I-2.11, P-6 of KPWD SR 2013-14)								
	Asphalt Road	Cum	1	2000.00	0.45	0.70	1400.00		
	Concrete Road		1	195.00	0.45	0.75	146.25		
	Asphalt Cross Cutting		320	7.50	0.45	0.70	1680.00		
	Concrete Cross Cutting		70	7.00	0.45	0.75	367.50		
	Total						3593.75	60.48	217350.00
	Basic Rate	56.00							
	Area weightage @ 8%	4.48							
	Total	60.48							